

Model MSX - Open view



MUA Mounted on Combo Curb Kit



Provides NPFA compliance for minimum distance between intake and exhaust.

Electric Heater



Heater control cabinets are installed completely within the heating section, factory wired up to 200kW.

Hot Water and Steam Coils



Coils have copper tubes with permanently expanded aluminum fins.

Evaporative Cooling Module



Galvanized steel housing. Evaporative Cooling media is Munters GLASdek.

Microprocessor Controller



Located in unit control center. Permits direct input without ancillary hardware or software.

Remote Interface



Used with Microprocessor Controller. Input new operating settings and displays alarm conditions.

Typical Industrial Remote Panel



May be selected in lieu of Microprocessor Controller. May contain remote interface.